

Jervoise Bay Boat Facility

Value \$3M



Works completed as Watpac Civil & Mining
Director's involvement – Tim Malseed – Project Manager

FACTS

Client	Dept. of Planning & Infrastructure	Division	Civil and Mining
Contact	Peter Boreham	Market	Coastal Infrastructure
Contract	AS 2124-1992	Commenced	July 2008
Location	Jervoise Bay, WA	Completion	October 2008

PROJECT OVERVIEW

Construction of a four-lane boat ramp at the Woodman Point recreational boating precinct in Jervoise Bay, located 10km south of Fremantle.

Works comprised of a floating pontoon jetty, mooring fence, access roads and car parks, drainage and rock revetment works.

SPECIFICATIONS

- 0 4,000m³ bulk earthworks
- 0 3,000m³ limestone revetment works
- 0 350m of stormwater drainage up to 4m deep
- 0 Supply and install 80 pre-cast concrete boat ramp slabs
- 0 Supply and install 13 concrete flexmets
- 0 Supply and drive 32 steel piles
- 0 Build two finger jetties and one mooring fence