

Denmark Dam Remedial and Flood Works

Value \$1.0M



Works completed as Watpac Civil & Mining

Director's involvement – Tim Malseed – Operations Manager/Pete Hancock – Project Manager

FACTS

Client	Water Corporation	Division	Civil and Mining
Contact	Joel McLure	Commenced	January 2017
Location	Denmark, WA	Completed	May 2017

PROJECT OVERVIEW

In late 2016, Watpac was awarded the contract to complete remedial works to the concrete weir at the Denmark Dam, located just out of Denmark in Western Australia, approximately 400 kilometres south-east of Perth.

The works include demolition, pipework, concrete works, steel works and scuba diving works.

SPECIFICATIONS

- Demolition and disposal of floodgate including diving works
- Reinforced Cast insitu Concrete installation - 105.5m³
- Polypipe installation - 56m
- Supply and install of stainless steel pipework and grid mesh.