

Boddington Dam Remedial Works

Value \$1 M



Works completed as Watpac Civil & Mining

Director's involvement – Tim Malseed – Operations Manager/Pete Hancock – Project Manager

FACTS

Client	Water Corporation	Division	Civil and Mining
Contact	Clarke Hendry	Commenced	February 2018
Location	Boddington, WA	Completed	June 2018

PROJECT OVERVIEW

The newly awarded Boddington Dam Remedial Works project for the Water Corporation is expected to commence in February 2018.

The project comprises of removal of an existing spillway and pipework, followed by clearing, excavation, foundation preparation, construction of a new concrete spillway and installation of new valves and pipework.

The project is expected to be completed by late May 2018.

SPECIFICATIONS

- $\approx 10,000\text{m}^2$ of clearing
- $\approx 5,100\text{m}^3$ of excavation
- $\approx 95\text{m}^3$ of special mix reinforced concrete installation
- Installation of a coffer dam for the outlet works
- Supply and installation of valves and 60m of draincoil and PE pipework