

# Mount Barker WWTP Contingency Overflow Pond



Value \$0.7M



Works completed as Watpac Civil & Mining

**Director's involvement – Tim Malseed – Operations Manager/Pete Hancock – Project Manager**

## FACTS

<b>Client</b>	Water Corporation	<b>Division</b>	Civil and Mining
<b>Contact</b>	Joel McClure	<b>Commenced</b>	February 2018
<b>Location</b>	Mount Barker, WA	<b>Completed</b>	May 2018

## PROJECT OVERVIEW

Watpac has recently been awarded the contract to perform construction works at the Wastewater Treatment Plant facility in Mount Barker, approximately 370km south-east of Perth.

The project involves the construction of a clay lined overflow storage pond connected to the existing polishing treatment pond via a buried concrete encased pipe at the Mt Barker Wastewater Treatment Plant.

Works are expected to be completed by April 2018.

## SPECIFICATIONS

- 14,600m<sup>2</sup> of clearing
- 4000m<sup>2</sup> of foundation preparation
- 3282 bank cubic metres of embankment construction
- Supply, installation and encasement of pond connection pipework
- 290m of chain link fencing