

Indian Ocean Drive Passing Lanes

Value \$2.6M



Works completed as Watpac Civil & Mining

Director's involvement – Pete Hancock – Project Manager/Tim Malseed – Operations Manager

FACTS

Client	Main Roads WA	Division	Civil and Mining
Contract	Schedule of Rates	Commenced	August 2012
Location	Shire of Gingin, WA	Completion	November 2012

PROJECT OVERVIEW

Construction of Passing Lanes and Intersection Improvements - Indian Ocean Drive

Watpac undertook the construction of two passing lanes and the improvement of an intersection, including removal of existing pavement, bulk earthworks, new pavement construction, two coat emulsion seal, culverts, line marking, kerbing and signage. Being a public road, traffic was the key challenge for this job and had to be managed around the works on the passing lanes and through the intersection during the various stages of improvement.

SPECIFICATIONS

- 0 3.90km total length of passing lanes and intersection works
- 0 16,000m³ of earthworks
- 0 25,000m² of limestone pavement
- 0 22,500m² of gravel road base
- 0 23,200m² of road seal
- 0 All associated culverts, linemarking, signage and kerbing