

Albany Highway Widening – Mount Barker Passing Lanes

Value \$2.2M



Works completed as Watpac Civil & Mining

Director's involvement – Pete Hancock – Project Manager/Tim Malseed – Operations Manager

FACTS

Client	Main Roads WA	Division	Civil and Mining
Contact	Available on request	Commenced	March 2016
Location	Mount Barker, WA	Completed	November 2016

PROJECT OVERVIEW

Watpac has undertaken the construction of two passing lanes, including removal of existing pavement, bulk earthworks, new pavement construction, pavement stabilisation, two coat emulsion seal, asphalt, culverts, line marking, kerbing and signage.

Construction during the wetter months of the year and being a public road presented two key challenges for this job that had to be managed around the works on the passing lanes during the various stages of improvement.

SPECIFICATIONS

- 4.3km total length of passing lane construction.
- 15,500m³ of earthworks
- 32,931m² of Subgrade
- 25,912m² of gravel subbase
- 22,642m² of gravel basecourse
- 81,000m² of pavement cement stabilisation
- 1,180m subsoil drainage
- 20,862m² of road sealing works
- 1,600m² of Asphalt works
- 118m culverts
- 1,202m kerbing
- All associated linemarking and signage.