

Access Roads and Carparks Upgrade - Kalbarri National Park

Value \$7.1M



Works completed as Watpac Civil & Mining
Director's involvement –Tim Malseed – Operations Manager

FACTS

Client	Department of Parks and Wildlife	Division	Civil and Mining
Contact	Rory Chapple	Commenced	December 2016
Location	Kalbarri, WA	Due for Completion	July 2017

PROJECT OVERVIEW

Watpac is upgrading 20 kilometres of unsealed roads/ tracks in the Kalbarri National Park to sealed roads for the Department of Parks and Wildlife (DPaW) in Western Australia. The project is located 30 kilometres east of Kalbarri – 570 kilometres north of Perth.

The Stage 2 Loop / Z Bend Access Roads and Carparks Upgrade Works has included earthworks, drainage, winning of pavement materials, pavement construction and carparks, with road sealing works scheduled for completion in July 2017.

The carpark completion works will be carried out later in the year following completion of other National Park infrastructure works being carried out by DPaW.

SPECIFICATIONS

- 0 Embankment - 71,778m³
- 0 Subgrade - 265,996m²
- 0 Basecourse - 214,544m²
- 0 Bituminous surfacing - 173,591m²
- 0 874m of Reinforced Concrete Box Culverts including cast insitu base slabs and headwalls