

Albany Highway Harold Road Passing Lanes



Value \$4.2M



Works completed as Watpac Civil & Mining

Director's involvement – Tim Malseed – Operations Manager/Pete Hancock – Project Manager

FACTS

Client	Main Roads Western Australia	Division	Civil and Mining
Contact	Arthur Phillips	Commenced	February 2017
Location	Kojonup, WA	Completed	June 2017

PROJECT OVERVIEW

Watpac was awarded the contract to reconstruct approximately three kilometres of Albany Highway in the Kojonup region.

The Works comprise of the construction of two passing lanes on Albany Highway within the Shire of Kojonup between, SLK240.38 to SLK 343.26. Specifically, the works comprised the following:

- 0 Reconstruction of 2.88 km of Albany Highway, comprising of bulk earthworks, a 700mm gravel pavement, a two-coat emulsion seal, underdrainage, kerbing, line-marking and signs.
- 0 Construction of ancillary drainage works, including 375, 450, and 900dia RCP's.
- 0 Construction side roads.

SPECIFICATIONS

• Foundation Preparation	≈50,000m ²
• Earthworks	≈80,000m ³
• Subgrade Preparation	≈75,000m ³
• Upper & Lower Subbase	≈120,000m ²
• Basecourse	≈48,000m ²
• 2 coat emulsion seal	≈47,000m ²
• Precast concrete culverts	≈230m
• Subsoil drainage and kerbing	≈720m