

# Construction of Miling Bypass Great Northern Highway

Value \$21.2 M



Works completed as Watpac Civil & Mining

**Director's involvement – Tim Malseed – Operations Manager/Pete Hancock – Project Manager**

## FACTS

<b>Client</b>	Main Roads WA	<b>Division</b>	Civil and Mining
<b>Contact</b>	David Clarkson	<b>Commenced</b>	April 2018
<b>Location</b>	Miling, WA	<b>Anticipated Completion</b>	Q1 2019

## PROJECT OVERVIEW

The Miling Bypass project is a road construction project to build a bypass road to the town of Miling, approximately 220km North East of Perth.

The project works include 9.3 kilometres of upgrade to the Great Northern Highway, 3.5 kilometres of intersections and side roads construction, bulk earthworks, drainage works, rock excavation, water service relocations, fencing, road furniture installation and revegetation works.

Traffic management will be installed to facilitate the construction works and the tie-ins to the new road alignments, with disruption to the town of Miling and traffic movements being kept to a minimum

## SPECIFICATIONS

- 0 ≈2,200m<sup>3</sup> of Contaminated material removed and disposed of offsite
- 0 ≈750m of Drainage Pipe Installation
- 0 ≈1,300m of Box Culvert Installation
- 0 ≈80,000m<sup>3</sup> of Pavement Construction
- 0 ≈61,000m<sup>3</sup> of Rock Excavation
- 0 ≈163,000m<sup>3</sup> of Embankment Construction
- 0 ≈145,000m<sup>2</sup> of Sealing Work