

Nova Nickel Waste Rock Pad Construction

Value \$1.4M



Works completed as Watpac Civil & Mining
Director's involvement –Tim Malseed – Operations Manager

FACTS

Client	Independence Nova	Division	Civil and Mining
Contact	Ken Riseham	Commenced	February 2017
Location	East of Norseman, WA	Completed	April 2017

PROJECT OVERVIEW

Watpac has completed the project to construct a waste rock dump and access roads adjacent to the ore pad.

Works included land clearing and topsoil and vegetation stockpiling, access roads construction, surface preparation, surface water management (contours and HDPE lined pond construction), pad construction, rehabilitation of old tracks and test pits.

SPECIFICATIONS

- 0 Foundation Preparation - 96,000m²
- 0 Construct low permeability clay layer - 45,250m³
- 0 Excavate and construct drainage sump - 19,100m³
- 0 Supply and install 1.5mm thick HDPE liner - 9,600m²
- 0 Basecourse - 4,900m²